


JWST Observatory Status



APS 16-17th July 2013


Mark Clampin - JWST Observatory Project Scientist

mark.clampin@nasa.gov

Goddard Space Flight Center



JWST Observatory









Optical Telescope Element: Optics



- JWST flight mirrors are all completed: Optical requirements are met

Mirror	Measured (RMS SFE)	Uncertainty (RMS SFE)	Total (RMS SFE)	Requirement (RMS SFE)
18 primary Segments (Composite Figure)	23.6	8.1	25.0	25.8
Secondary	14.7	13.2	19.8	23.5
Tertiary	18.1	9.5	20.5	23.2
FSM	13.9	4.9	14.7	18.7



- Mirrors will have completed shipping to GSFC by year's end









Aft-Optics System



- Completed the Aft Optics System (w/Tertiary and Fine Steering Mirrors)
 - 3 cryogenic cycles with alignment measurements completed.
 - Stored at Ball until 2015, when it will be installed in the Pathfinder for tests






Optical Telescope Element: Backplane



- Primary Mirror Backplane comprises four elements
 - Primary mirror backplane assembly (PMBA)
 - PMBA center section(CS) + 2 PMBA wings
 - Backplane Support fixture which houses ISIM and supports PMBA




- For JWST the critical path runs through the Optical Telescope Element and production of the telescope backplane.



Optical Telescope Element: Backplane




- **PMBA and BSF construction at ATK is complete**
- **PMBA wings have completed cryogenic cycling tests with Omni**
 - ➔ Tested in XRCF chamber: hardware achieved 23 K – 32K
 - ➔ Factoid: Mass difference of wings is 0.005 kg (50.130 kg vs 50.125 kg).
 - ➔ Currently undergoing post-test ultrasonic and visual inspection of joints.
- **PMBA center section (CS) has been mated with support fixture BSF**
 - ➔ Scheduled to begin cryocycle testing at XRCF ~September 2013
- **Ships to GSFC to begin telescope integration ~April 2015**



Mounting a dummy mirror segment using the robot arm



WEST








JWST's Spacecraft Bus



- **Spacecraft Bus systems include:**

- ➔ Power/Electrical System
- ➔ Attitude control systems
- ➔ Propulsion
- ➔ Communications
- ➔ MIRI Cryocooler
- ➔ OTE/Sunshield interface



- **Key milestone for the Observatory is the Dec 2013 Critical Design Review**


- **Spacecraft Cone is load-bearing structure for the bus**

- ➔ Constructed from composite material
- ➔ Preparing to cut harness/hardware pass-through apertures






Sunshield Status



- **Template (flight-like) constructed and delivered to NGAS: Major goals:**
 - ➔ **Verify 3-D shape for each layer under tension**
 - ➔ **repeat w/deployment fixtures on layer 5**
 - ➔ **Verify hole punching strategy & hole alignment concept**
 - ➔ **Verify folding/stowing concept on IVA facility**





Sunshield Mockup/test Facility (IVA)



Folded sunshield layers



Sunshield Layer 3 Template






OTE/ISIM Integration & Test Flow



JWST OTIS Integration and Test




Acronyms


- AOS: Aft-Optics Subsystem
- GSE: Ground Support Equipment
- MGSE: Mechanical Ground Support Equipment
- NGAS: Northrop Grumman Aerospace Systems
- OGSE: Optical Ground Support Equipment
- PF: Pathfinder

Legend

- Prep & Transport (Blue)
- Assembly / Integration (Orange)
- Functional / Test (Green)
- Delivery (Yellow)



Flight OTIS I&T






Chamber-A: OTIS Test Configuration



Chamber Isolator Units

Isolates the Ground Test from Seismic activities for Optical Testing




Center of Curvature Optical Assembly (COCOA)

- Multiwavelength interferometer (MWIF), null, calibration equipment, coarse/fine PM phasing tools, Displacement Measuring Interferometer
- Build and Tested – in Storage at MSFC/XRCF



3 Auto Collimating Flat Mirrors (ACFs)


- Three - 1.5 meter mirrors and actuators for Pass and Half testing



Cryo Position Metrology (CPM) PG Cameras in canisters


AOS Source Plate and Cable Support

- Fiber optic sources for Field Testing and pas and Half Testing



Space Vehicle Thermal Simulator (SVTS) and Sunshield Simulator

Absolute Distance Measurement Assembly (ADM)




Deep Space Edge Radiation Sink (DSERS) – GSE Radiators for collecting Flight Heat during the OTIS test



Chamber-A Refurbishment



- Re-outfitting JSC's Chamber A to meet the testing requirements.
- Chamber functional modifications completed June 2012
 - ➔ Checked out with a chamber functional test (July – Aug. 2012)
- Cleanroom Assembly will be finished fall 2013






Deployment Concept




- Deployment Review Team convened by NGAS to monitor implementation of JWST deployment at system-level







OTE Deployment Hardware Testing



- Completed Successful Qualification testing of the EQM SMSS Mid-Hinge Deployment Assembly
- Completed Cryo and Vibe-testing of the EQM SMSS In-Board Hinge (IBH) Deployment Mechanism
- Completed Initial Build and testing of EQM Primary Mirror Backplane Assembly (PMBA) Wing Deployment Mechanism
- Delivered EQM DTA to NGAS and began initial testing



SMSS EQM Mid-Hinge in Cryo-Test




PMBA EQM Hinge



Project Scientist Watch List Examples



- **Observatory alignments are a focus area as we enter I&T phase**
 - ➔ **Thermal Stray Light (Telescope ➔ Spacecraft alignment):**
 - ➔ **Secondary mirror (SM) view to sunshield (known as Light lines)**
 - ➔ **Layers have to align so that SM only views the top (coldest) layer**
 - ➔ **Sunshield layer to layer alignment**
 - ➔ **SM alignment to the boresight**
 - ➔ **Star Tracker ➔ Telescope alignment**
 - ➔ **Alignment relative to the observatory boresight**
 - ➔ **Envelope: Design envelope requirements before/during deployment**
- **NIR and Stray Light**
 - ➔ **Focus on I&T and contamination control for NIR stray light control**
 - ➔ **Primary is particulate contamination on telescope optics**
- **Image Motion/Pointing: Focus on implementation to**











Deployment Testing



- **Observatory integration and deployment testing is complex, and bears directly upon science performance as well as deployment success**
- **First opportunity to exercise full system end-to-end**
 - ➔ **Approach**
 - ➔ **Sub-system to full scale deployments**
 - ➔ **Full scale deployments with flight hardware**
- **Early use of full-scale mockups and deployment tests**
 - ➔ **investigate potential snags and clearances**
 - ➔ **alignment strategy**
- **Multiple full scale deployments will exercise flight system**



Spacecraft/Sunshield I&T



Install core to Bus



Install and Align Mid Booms

Install and Align Forward and Aft Structures

Skeleton Deployed Align and Shim Adjust


Skeleton Stow

Skeleton Deployment Test








Spacecraft/Sunshield I&T





Spacecraft/Sunshield I&T





Summary



- JWST Observatory is executing to Baseline



- Project Science closely integrated with major areas impacting scientific performance

